
# Vadose Zone Characterization of B-BX-BY Waste Management Area and Surrounding Disposal Facilities, Hanford Site, Washington


S.M. Sobczyk, P.D. Henwood, and R.G. McCain S.M. Stoller Corporation\*
Richland, Washington

J.M. Silko
U.S. Department of Energy Richland Operations Office
Richland, Washington









Locations of B-BX-BY
Waste Management
Area and Surrounding
Waste Disposal
Facilities at Hanford
Site (modified from
Narbutovskih 2000)

### Background

- \*\* DOE Grand Junction Office asked by DOE Richland Operations Office in 1994 to establish baseline vadose zone characterization project at Hanford single-shell tank farms
- \* Project utilized geophysical logging capabilities and experience established during former National Uranium Resource Evaluation (NURE) program
- \*\* Logged 769 boreholes and completed baseline characterization of Hanford single-shell tank farms from 1995 to 2000
- \*\* Initiated baseline characterization logging in waste disposal sites of Hanford 200 Areas in 2001

### Waste Disposal Site Baseline Characterization

- Employs same data analysis, interpretation, and reporting methodology as tank farm baseline characterization
- Integrates log data from all available boreholes to interpret subsurface contamination
- \* Assembles pre-baseline (historical) log data and compares to baseline to assess contaminant stability over time
- Completed logging in 2002 of more than 260 boreholes in B-BX-BY Waste Management Area and surrounding waste disposal facilities in 200 East Area of Hanford Site


### Capabilities of Logging Systems

- \* Spectral Gamma Logging System (SGLS)
  - HPGe detectors (liquid nitrogen cooled)
  - 35% and 70% relative efficiencies
  - $10^{-1}$  to  $10^4$  pCi/g ( $^{137}$ Cs)
- High Rate Logging System (HRLS)
  - 8-mm x 6-mm "planar" HPGe detector (liquid nitrogen cooled)
  - Internal and external shields to extend range
  - 10<sup>3</sup> to 10<sup>9</sup> pCi/g (<sup>137</sup>Cs)


### Capabilities (continued)

- \*\* Neutron Moisture Logging System (NMLS)
  - Standard moisture gauge with AmBe source and <sup>3</sup>He detector
  - Specialized calibration functions for determination of volumetric moisture content in 6-in. and 8-in. steel-cased boreholes
  - Not part of baseline characterization


### **B-BX-BY** Waste Management Area, Surrounding Waste Disposal Facilities, and Boreholes



#### **BX Tank Farm Under Construction**




### Types of Waste Disposal Facilities Near B, BX, and BY Tank Farms




- \* Trenches
- \* Cribs and tile fields
- \* French drains
- \* Reverse wells
- Unplanned releases(UPRs)

### Volume of Waste Discharged to Vadose Zone in B-BX-BY Area (modified from PNNL 2003)




Total Uranium
Released to Vadose
Zone in Kilograms
(Simpson et al. 200


#### General Stratigraphy of B-BX-BY Waste Management Area (modified from Wood et al. 2000)




### Waste Disposal Facilities, and Location of Cross Section A–A' (modified from Horton 2002)




# Cross Section A-A': Contamination and Interpreted Stratigraphy in Dip Direction in B-BX-BY Area and Surrounding Waste Disposal Facilities



### Cross-Section A-A' (continued): B-BX-BY Area and Surrounding Waste Disposal Facilities




### Borehole 299-E33-41 SGLS Compared to Prior Logging



- \* Logged in 1991, 1997, and 2002
- Radionuclide Logging
  System (RLS) used in
  1991 and 1997
- Significant influx of uranium contamination between log depths of 120 and 247 ft
- Influx occurred between 1991 and 1997

# Borehole 299-E33-18 SGLS Compared to Prior Logging





- \* Logged in 1992, 1997, and 2002
- \* 1992 gross gamma log indicated high total counts between log depths of 230 and 242 ft
  - Based on the gross gamma log,
     RLS used to take stationary
     measurements for 300 s at
     236 and 252 ft
  - 60Co detected at both depths at less than 3 pCi/g
  - No other man-made radionuclides detected

### Borehole 299-E33-18 SGLS Compared to Prior Logging (continued)

- Uranium detected in 1997 and 2002 at log depths between 234 and 254 ft
  - Influx of uranium occurred between 1992 and 1997
  - Possible increase between 1997 and 2002


### Visualization of <sup>238</sup>U Contamination Near Tank BX-102 (modified from DOE 2002)






Uranium
Concentrations
in 1994 in
Groundwater
Samples in
200 East Area
(modified from
PNNL 1995)


# Samples From Wells in Vicinity of B-BX-BY Waste Management Area (PNNL 1998)




# Average Uranium Concentrations in Groundwater Samples in 1997 in B-BX-BY Waste Management Area (data from PNNL 2002)




### Average Uranium Concentrations in Groundwater Samples in 1998 in B-BX-BY Waste Management Area (data from PNNL 2002)



Single-shell tank (assumed leaker)




Uranium
Concentrations
in Groundwater
Samples in 2000
in B-BX-BY Area
(modified from
PNNL 2001)



Uranium
Concentrations
in Groundwater
Samples in 2002 in
B-BX-BY Waste
Management Area
(PNNL 2003)

# Waste Management Area and Surrounding Waste Disposal Facilities



#### **Conclusions**

- Log data of B-BX-BY Waste Management Area detected processed uranium only near tank BX-102 and in borehole 299-E33-59 (near 216-B-7B Crib)
- Based on log data, uranium concentrations in the deep vadose zone increased in boreholes 299-E33-41 and 299-E33-18 between 1991 and 1997
- First reported increase in uranium concentration in groundwater detected in samples from borehole 299-E33-18 in January 1994

#### Conclusions (continued)

- \* A southeast–northwest-trending uranium plume developed in the groundwater since 1994
- Wranium contamination originating at or near tank BX-102 traveled through vadose zone to northeast and entered the groundwater; uranium in groundwater moved northwest and probably reached groundwater underneath 216-B-61 Crib
- Sources of deep <sup>60</sup>Co contamination detected in borehole 299-E33-9, underneath tank BY-103 (BY Tank Farm), and in borehole 299-E33-13 are tank leaks either in BY Tank Farm or in BY Cribs

#### For More Information

\* Vadose Zone Characterization Web Page

http://www.gjo.doe.gov/programs/hanf/HTFVZ.html

### Bibliography

- General Electric Company, 1951. *Hanford Works Monthly Report for February 1951*, HW–20438, General Electric Company, Richland, Washington, March.
- Horton, D.G., 2002. Borehole Data Package for Calendar Year 2001 RCRA Wells at Single-Shell Waste Management Area B-BX-BY, PNNL-13827, Pacific Northwest National Laboratory, Richland, Washington.
- Narbutovskih, S.M., 2000. Groundwater Quality Assessment Plan for Single Shell Waste Management Area B-BX-BY at the Hanford Site, PNNL-13022, Pacific Northwest National Laboratory, Richland, Washington.
- Pacific Northwest National Laboratory (PNNL), 1995. Hanford Site Groundwater Monitoring for 1994, PNL-10698, prepared by Pacific Northwest Laboratory for the U.S. Department of Energy Richland Operations Office, Richland, Washington.
- PNNL, 1998. *Hanford Site Groundwater Monitoring for Fiscal Year 1997*, PNNL–11793, prepared by Pacific Northwest National Laboratory for the U.S. Department of Energy Richland Operations Office, Richland, Washington.
- PNNL, 1999. *Hanford Site Groundwater Monitoring for Fiscal Year 1998*, PNNL–12086, prepared by Pacific Northwest National Laboratory for the U.S. Department of Energy Richland Operations Office, Richland, Washington.
- PNNL, 2000. *Hanford Site Groundwater Monitoring for Fiscal Year 1999*, PNNL–13116, prepared by Pacific Northwest National Laboratory for the U.S. Department of Energy Richland Operations Office, Richland, Washington.
- PNNL, 2001. *Hanford Site Groundwater Monitoring for Fiscal Year 2000*, PNNL–13404, prepared by Pacific Northwest National Laboratory for the U.S. Department of Energy Richland Operations Office, Richland, Washington.

#### Bibliography (continued)

- Pacific Northwest National Laboratory (PNNL), 2002. *Hanford Site Groundwater Monitoring for Fiscal Year 2001*, PNNL–13788, prepared by Pacific Northwest National Laboratory for the U.S. Department of Energ Richland Operations Office, Richland, Washington.
- \*\* PNNL, 2003. *Hanford Site Groundwater Monitoring for Fiscal Year 2002*, PNNL–14187, prepared by Pacific Northwest National Laboratory for the U.S. Department of Energy Richland Operations Office, Richland, Washington.
- Routson, R.C., 1973. A Review of Studies on Soil-Waste Relationships on the Hanford Reservation from 1944 to 1967, BNWL-1464, Battelle Pacific Northwest Laboratory, Richland, Washington.
- Simpson, B.C., R.A. Corbin, and S.F. Agnew, 2001. *Hanford Soil Inventory Model*, BHI–01496, Rev. 0, Bechtel Hanford, Inc., Richland, Washington.
- \*\* U.S. Department of Energy (DOE), 1993. *B Plant Source Aggregate Area Management Study Report*, DOE/RL–92–05, Rev. 0, U.S. Department of Energy Richland Operations Office, Richland, Washington.
- ★ DOE, 1997. Vadose Zone Characterization Project at the Hanford Tank Farms, BY Tank Farm Report, GJO-96-2-TAR, GJO-HAN-6, prepared by MACTEC-ERS for the Grand Junction Office, Grand Junction, Colorado.
- \*\* DOE, 1998. Vadose Zone Characterization Project at the Hanford Tank Farms, BX Tank Farm Report, GJO-HAN-19, prepared by MACTEC-ERS for the Grand Junction Office, Grand Junction, Colorado.
- DOE, 2000a. *Hanford Tank Farms Vadose Zone, B Tank Farm Report,* GJO–99–113–TAR, GJO-HAN–28, prepared by MACTEC–ERS for the Grand Junction Office, Grand Junction, Colorado, September.
- ➡ DOE, 2000b. Hanford Tank Farms Vadose Zone, Addendum to the BX Tank Farm Report, GJO−98−40−TARA, GJO−HAN−19, prepared by MACTEC-ERS for the Grand Junction Office, Grand Junction, Colorado, July.

#### Bibliography (continued)

- DOE, 2000c. Hanford Tank Farms Vadose Zone, Addendum to the BY Tank Farm Report, GJO-96-2-TARA, GJO-HAN-6, prepared by MACTEC-ERS for the Grand Junction Office, Grand Junction, Colorado, September.
- DOE, 2000d. 200–TW–1 Scavenged Waste Group Operable Unit and 200-TW-2 Tank Waste Group Operable Unit RI/FS Work Plan, DOE/RL–2000–38, Draft A, Richland Operations Office, Richland, Washington.
- DOE, 2002. 216–B–8 Crib and Adjacent Sites Waste Site Summary Report, GJO–2002–343–TAC, prepared by S.M. Stoller Corporation for the Grand Junction Office, Grand Junction, Colorado, September.
- Wood, M.I., (Fluor Hanford, Inc.), T.E. Jones (CH2M Hill Hanford Group, Inc.), R. Schalla, B.N. Bjornstad, S.M. Narbutovskih (PNNL), 2000. *Subsurface Conditions Description of the B-BX-BY Waste Management Area*, HNF–5507, CH2M Hill Hanford Group, Inc., Richland, Washington.